

SCOPE OF WORK

1.01 Description

The project consists of improvements to Cherry Hill Boulevard between NJSH Route 38 and Monmouth Drive in the Township of Cherry Hill, Camden County, New Jersey.

1. The roadway improvements will include variable depth milling up to a 3" maximum of the existing hot mix asphalt. Contractor to install two (2) inches of hot mix asphalt surface course 9.5M64 to match existing elevations unless otherwise indicated on the plans.
2. Hot Mix Asphalt Pavement Repair as directed by the Engineer after milling.
3. The installation of concrete vertical curb, concrete sidewalk, concrete driveways, and other incidental work as directed by the Engineer.
4. The installation of ADA compliant curb ramps at various locations as directed by the engineer. Separate payment will not be made for truncated domes, brick pavers, installation of concrete sidewalk necessary for transition to the ramp, up to thirty linear feet (30') of concrete curb, concrete headers, hot mix asphalt pavement repair associated with curb installation, the ramp landing or other items associated with the construction of the ADA compliant curb ramps. However, all costs shall be included in the unit price bid of the item *ADA Curb Ramp*.
5. All related incidental work, including earthwork, traffic control, dust control, soil erosion and sediment control, cleaning and restoration.
6. Sanitary manholes are to be rehabilitated and made waterproof along with ladder rung replacement as noted in the plans and specifications.
7. Reset manholes, castings, and vent/valve boxes.
8. Replace existing curb inlet head pieces with Eco Type "N" head pieces and existing inlet grates with bicycle safe grates.
9. The contractor is responsible for verifying the location of all utilities and for scheduling all work involved with utilities directly. All costs related to his coordination shall be included in the various items of his bid.
10. Topsoiling, fertilizing and seeding will be placed at all disturbed areas. Areas affected by the proposed work will be regraded.
11. The Contractor shall ensure residents/businesses have access to their homes/businesses during construction. This work shall be included in the various items in the proposal.
12. Tree removal to be performed where shown on plans. Provide borrow topsoil as necessary.
13. Contractor shall be responsible for providing all necessary traffic control to protect workers and work area for each location. As per Cherry Hill Township Ordinance all contractors working within roadways in Cherry Hill are required to submit a Traffic Control Plan (TCP) detailing the scope of work and any proposed detours for review and approval of the Cherry Hill Township Police Department prior to the start of construction. Also included in the Ordinance is a requirement that an on-site preconstruction meeting be held to review the

project. The Traffic Control Plan must meet or exceed the requirements of the MUTCD and be submitted a minimum of 72 hours prior to the start of construction to allow for review and adequate notice to the motoring public. Separate payment will not be made but all costs shall be included in the various items in the proposal.

14. No work shall be performed before 7:30 a.m. on weekdays. Contractor shall notify in writing Engineer at least forty-eight (48) hours in advance of any work on Saturdays. No work shall be performed before 8:00 a.m. on Saturdays. There will be no work permitted on Sundays or holidays. This project will receive inspections and the normal working hours for the Inspector are from 8:00 AM to 4:30 PM, Monday through Friday. Any overtime inspection costs which are avoidable will be reimbursed by the contractor.
 15. Any existing house number painted along the curb which are removed as a result of the construction shall be repainted with stencils using white, reflective paint. Separate payment for painting will not be made; however, all costs associated shall be included in the cost of the various items in the proposal.
- 1.02 The above Scope of Work outlines the general items and shall not be construed as being all-inclusive.
 - 1.03 The contractor shall obtain and pay for a NJDOT road opening permit for any work impacting NJSH Route 38 as required. No separate payment.
 - 1.04 The Township of Cherry Hill reserves the right to modify the scope of work by adding and/or deleting roadway segments.
 - 1.05 The plans entitled " FY2018 NJDOT Trust Fund Reconstruction of Cherry Hill Boulevard - Phase 1" Township of Cherry Hill, Camden County, New Jersey are appended hereto and are now made part of these specifications.
 - 1.06 Construction of this project is anticipated to begin Spring 2019. Owner reserves the right to delay work, if necessary due to weather concerns. Extension of work shall not be cause for additional costs to the Owner, regardless of potential duplicate mobilization.

END OF SCOPE OF WORK